

Sea Water Storage Tank

Project: Paspaley Pearls

Category: Primary Containment –
Potable Water

Completion

Date: October 2006

Product: Rhino Linings Tuff Stuff



Job Description

Paspaley required replacement of a damaged liner in a tank used to store seawater for the culture of pearls. They required a product that was suitable for potable water and Rhino Linings Tuff Stuff was the answer to their problem.

The tank was 4.7 mtr high, the roof needed to be removed and the internals sand blasted before applying the material. The tank was sprayed in Tuff Stuff with a geotextile floor base.

The remote location of the project (Broome) and the availability of sub labor and freight into and out of the site presented a unique challenge in order to complete the job on time and within budget.

Management of Paspaley commended the Rhino Linings team for their professional attitude and pride in work, the project was completed ahead of time and the site left clean and tidy to Paspaleys standards.

